

令和4年度

準用河川外城田川災害防止対策工事（その3）

数 量 計 算 書



工 種	種 別	細 別	規 格	単位	計 算 数 量	設 計 数 量	摘 要
土 工	掘 削			m <sup>3</sup>	84	80	
	盛 土		(購入土)	m <sup>3</sup>	72	70	
	盛 土	仮設盛土	(搬入土)	m <sup>3</sup>	450	450	
	床 堀			m <sup>3</sup>	42	40	
	埋 戻 し	流用土		m <sup>3</sup>	58	60	
	残 土 処 分	残土運搬	BH積込み 運搬距離8.0km以下	m <sup>3</sup>	62	60	(84.0+42.0)-58.0/0.90
		仮設盛土運搬 (搬入土)	BH積込み 運搬距離3.5km以下	m <sup>3</sup>	500	500	450.0/0.90
法 面 工	表 土 は ぎ			m <sup>3</sup>	42	40	
	法 面 整 形 工			m <sup>2</sup>	96	100	
	張 芝 工		野芝	m <sup>2</sup>	46	50	
	人 工 張 芝 工			m <sup>2</sup>	50	50	
護 岸 工	かご工	2.0×1.0×0.5 9段		式 (m <sup>2</sup> )	1 (100)	1	
構造物撤去工	構造物撤去	無筋コンクリート		m <sup>3</sup>	18	18	
	殻運搬処理	無筋コンクリート		m <sup>3</sup>	18	18	
仮 設 工	仮締切工	大型土のう	土砂搬入, 制作, 設置 (搬入土)	袋	86	86	
		大型土のう	撤去, 土砂撤去 (搬入土)	袋	86	86	

[illegible]



土 工 各 種 数 量 計 算 書

床掘り

測 点	距 離	右岸側									摘 要
		断面	平 均	数 量	断面	平 均	数 量		平 均	数 量	
NO.0+162.0	—	2.1	—	—							
+182.0	20.0	2.1	2.10	42.0							+192.00参照
小 計	20.0m			42.0m <sup>3</sup>							







土 工 各 種 数 量 計 算 書 仮設盛土											
測 点	距 離	仮設盛土									摘 要
		断面	平 均	数 量	幅	平 均	数 量		平 均	数 量	
NO. 0+162. 0	—	8. 2	—	—							
+182. 0	20. 0	8. 2	8. 20	164. 0							+192. 00参照
		8. 2	—	—							
(坂路部)											
NO. 0+142. 0	—	0. 0	—	—							
+156. 0	14. 0	14. 3	7. 15	100. 1							
+182. 0	26. 0	0. 0	7. 15	185. 9							
小 計	20. 0	m		450. 0	m3						

表土はぎ

測点	距離	右岸側									摘要
		断面	平均	数量	断面	平均	数量		平均	数量	
NO.0+162.0	—	2.1	—	—							
+182.0	20.0	2.1	2.10	42.0							+192.00参照
		2.1	—	—							
小計	20.0m			42.0m <sup>3</sup>							







## カゴ工(9段)

数量算出表

カゴ工展開図(右岸)



## カゴ工標準断面図



1式あたり

[illegible]

土 工 各 種 数 量 計 算 書 構造物とりこわし工

測点	距離	Co取壊し 右岸側									摘要
		断面	平均	数量	断面	平均	数量		平均	数量	
NO.0+162.0	—	0.9	—	—							
+182.0	20.0	0.9	0.90	18.0							+192.00参照
		0.9	—	—							
小計	20.0m			18.0m <sup>3</sup>							

大型土のう・敷鉄板・掛樋・敷碎石

[illegible]